

## NOTES:

- 1. FOR LAYOUT WITH ITS HUB CABINET, SEE ITS-3A.
- 2. ITS INTERSECTION COMMUNICATIONS CABINET PER CURRENT CITY OF FRESNO QUALIFIED PRODUCT LIST. (QPL)
- 3.  $6-1\frac{1}{2}$ " ITS CONDUITS INSTALL PER STD PLAN ITS-5, TYP.
- 4.  $2-1\frac{1}{2}$ " ITS CONDUITS INSTALL PER STD PLAN ITS-4, TYP.
- 5. FOR EXISTING TRAFFIC SIGNAL CONTROLLER STUB  $1\frac{1}{2}$ " CONDUIT INTO HOMERUN 6E PULLBOX.
- 6.  $4-1\frac{1}{2}$ " ITS CONDUITS INSTALL PER STD PLAN ITS-4, TYP.
- 7. 4'x7' ITS VAULT, SEE STD PLAN ITS-13.
- 8. FOR TRAFFIC SIGNAL EQUIPMENT LAYOUT, SEE STD PLAN E-24.

REF. & REV.

FFB 08

CITY OF FRESNO

ITS-3