

- FURNISH AND INSTALL 1 8' GROUND ROD FOR POWER UNIT.
- FURNISH AND INSTALL 4 8' GROUND RODS FOR GROUND GRID
- FURNISH AND INSTALL 4 9" FLOWER ROUND HAND HOLES, LID INSCRIBED "GROUND" #2 AWG BARE TINNED WIRE

NOTE: CLAMPS WILL NOT BE ALLOWED, ALL CONNECTIONS SHALL BE CAD WELDS

HUB FOUNDATION GROUNDING DETAILS

REF. & REV.

FEB 08

CITY OF FRESNO

08 ITS-22